




NOTES

1. The contractor shall provide adequate overlap of the plate on asphalt to assure that there is no slippage of the plate and no collapsing of the trench. The overlap shall not be less than half of the trench width.
2. Plates shall have skid resistant surface.
3. Plates shall be welded and secure on all arterial streets.
4. Minimum plate size of 4'x4'x1" can be used on excavation of 2' wide or 2 square feet. Larger plates are required for any excavation larger than those listed above. Plates smaller than 4'x4'x1" are not allowed.

DRAWN <u>JM</u> DATE <u>8/30/11</u>	CITY OF FULLERTON ENGINEERING DEPARTMENT	<u>REVISED</u> DATE <u> </u>
STD. NO. 314	TRENCH PLATING	
	APPROVED <u><i>DK</i></u> DIRECTOR OF ENGINEERING	DATE <u>11-2-11</u>