

- Concrete to be kept moist for 7 days, or curing compound may be used with approval of the Director of Engineering.
- 5. Sidewalk to be rotor trowel finished, or hair broomed. Driveway and gutter finish to be floated or broomed.
- 6. Distance between curb or sidewalk expansion joints to be 20' maximum or as directed by the Engineer.
- Scoring lines shall correspond with the scoring lines in existing adjacent sidewalk.
- All concrete to be removed shall be sawcut as directed.
- 9. Driveways, including X distance, shall not encroach into intersection curb return except as approved by the Director of Engineering.
- IO. No onsite drainage allowed to flow over driveway approach. Drainage must be intercepted and drained through curb face or storm drain if available.
- II. For removal and replacement of concrete items abutting A.C. pavement, a minimum width of 12" of A.C. shall be sawcut and removed adjacent to the construction. The A.C. pavement shall be replaced within 48 hours of the concrete pour, unless a longer time is approved by the Engineer prior to any removal
- Utility meters and pullboxes shall not be in the driveway approach. Street trees, street lights, power poles, fire hydrants, etc. shall be a minimum 7' clear from Top of "X" of driveway.

