





3" & LARGER WATER METER INSTALLATION

STANDARD DETAIL	REVISIONS								
603	NO.	DATE	NO.	DATE					
	1	12/01/00	4	02/28/17					
	2	02/13/13	5	04/20/22					
	3	02/29/16							
SHEET 1 OF 2					 CITY ENGINEER	5/9/2022 DATE	 PUBLIC WORKS DIRECTOR	5/24/2022 DATE	
DEPARTMENT OF PUBLIC WORKS									


LIST OF MATERIALS

- ① 90° DI Elbow, FLG x MJ
- ② Restraint device
- ③ DIP Spool, Class 53, FLG (order to size)
- ④ Compact DI Tee, FLG
- ⑤ 2" x 9" OD Reducing flange
- ⑥ 2" Brass ball valve, M-IPT x F-IPT with locking ear, 360° turn
- ⑦ 2" Brass plug, IPT
- ⑧ Resilient-seated gate valve with hand wheel, non-rising stem, FLG
- ⑨ Restrained flange adapter
- ⑩ DIP Spool, Class 53, FLGxPE (order to size)
- ⑪ 4" x 3" x 8"L DI concentric reducer, FLG
- ⑫ Water Meter
- ⑬ Reduced pressure principle backflow assembly.
- ⑭ 90° Compact DI Elbow, FLG
- ⑮ Adjustable pipe saddle support
- ⑯ Concrete pad, 4" Slab, Class 520-C-2500 (light broom finish), 2% slope towards sidewalk
- ⑰ ⅛" Full face inserted rubber flange gasket

Typical 3" Meter Connection



Typical 4" Meter Connection




NOTES

1. Refer to the City of Fullerton's Approved Materials List for approved manufacturers and model numbers.
2. Install water meter per manufacturer's specifications.
3. All steel bolts and nuts to have electrodeposited coating of zinc.
4. See Section 5-10 of these specifications for painting requirements.
5. Large meter assemblies installed in easements, roads and streets without curbs or with rolled curbs shall be protected by guard posts as shown on plans or as directed by Engineer per Standard Drawing 615.
6. Location of the large meter/backflow device assembly, and all parts must be approved by Engineer prior to installation. Failure to comply may result in project delays to correct all unacceptable/unapproved work. A wye strainer or hose bibb are not allowed to be installed on backflow assembly piping.
7. New backflow must be tested by a Orange County Certified backflow tester.

3" & LARGER WATER METER INSTALLATION



REVISIONS			
NO.	DATE	NO.	DATE
1	12/01/00	4	02/28/17
2	02/13/13	5	04/20/22
3	02/29/16		


 CITY ENGINEER 5/9/2022 DATE


 PUBLIC WORKS DIRECTOR 5/24/2022 DATE

STANDARD DETAIL

603

SHEET 2 OF 2

DEPARTMENT OF PUBLIC WORKS